

**THE BLUFF WILDERNESS HIKING TRAIL CAPITAL QUOTATION (2) – 2009**

**TO:**

**Wooden River Watershed Environment Organization**

Unit 14 Box 300, 3650 Hammonds Plains Road, Upper Tantallon, N.S. B3Z 4R3

Attn: Richmond Campbell

Email: Richmond.Campbell@dal.ca

Phone: 902-489-0457

**FROM:**

Company Name: \_\_\_\_\_

Date: \_\_\_\_\_

Contact: \_\_\_\_\_

Phone: \_\_\_\_\_

Email: \_\_\_\_\_

Please provide a fixed price for each piece of work detailed below **by midnight Saturday October 17, 2009**. One contractor will be awarded all the work on a total price based on what can be done within the annual budget. Prices must include all labour, materials, equipment rental or maintenance, oil, gas, blades, transportation of materials plus applicable taxes. Contractor must confirm Workers Compensation coverage and successful bidder will be required to provide a letter in good standing. All work must be carried out in compliance to the HRM Workplace Safety Procedures.

Confirmation of Workers Compensation Coverage: \_\_\_\_\_

Commitment to comply with HRM Workplace Safety Procedures \_\_\_\_\_

For contractors who have not done work previously for WRWEO, **three** references should be given with names, addresses (including email), and phone numbers

**A. Stone Tread Trail Construction**

Specifications (weights of stone are approximate)

Specified wet areas are to be re-treaded with whole, found stones in the immediate vicinity of the area to form a stable, durable, and safe path across areas. The treated area must be excavated to solid base subsoil to remove all organic material that could compromise the structure. Anchor stones (50-100 lbs, minimum surface area of 1.5 sq. ft. and 6" depth) every 3-6 feet, with smaller rock (10-30 lbs) between the anchors and wedged into a positions that are stable and suitably level for hiking and that permit drainage. Smaller rock and sandy soil may be used between medium sized rocks provided

they increase integrity of whole and do not compromise drainage. Stone/soil must be chosen to create minimal or no negative impact on the landscape.

**Stone tread trail construction is to be applied to twelve wet areas: Sites A, B, C, D, E, and F on loop 3 and Sites G, H, I, J, K, and L on loop 4, in locations given on the internet at:**

<http://wrweo.ca/capitalworksites/>

**This website provides GPS coordinates, photographs, distances, notes, and a map for the twelve capital work sites on loops 3 & 4: The Bluff and the Hay Marsh.**

Fixed price to include all design, labour, materials and required tools. If further information is required, please contact Richmond Campbell.

**FIXED PRICE – SITES A, B, C, D, E, and F:** \_\_\_\_\_

**FIXED PRICE – SITES G, H, I, J, K, and L:** \_\_\_\_\_

**Terms:**

1. Scope of Contract for capital work will be awarded based on approved budget from HRM. Contract will be awarded by October 20, 2009. All work must be completed by November 30, 2009. Should work not be completed by the deadline, WRWEO reserves the right to terminate the contract and award remaining work to an alternate contractor.
2. No extras will be paid by WRWEO without prior written approval for a change of scope to the defined work.
3. All travel costs must be included in quoted fixed prices.
4. Payment Terms: On completion and sign off of work, contractor will submit invoice to WRWEO. WRWEO will immediately submit this invoice to HRM for payment. Payment will be forwarded to the contractor immediately upon receipt from HRM.

**Acceptance:** Approval of Proposal and Contract Award

This proposal is accepted under the terms and conditions as a contract to proceed with the work:

Accepted by WRWEO:

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

Title